Sl No	Description of item	Unit	No	L	B	D	Qty	Rate	Amount
25	Refilling the basement and pipeline treanches with secleted available earthe for trench excavation including authority condition in layers from thedi including disponsary of the sunplus earth with a heavy 200 mtrs **Page No. 3 / Item No. 1.6 / PRED SR 2012-13**	Cum							
			Qty. Vide Item No. 23				**363.96**	61.00	**22202.00**
	Basic Rate	61.00							
	Sub Total A								**1616090.00**
26	KSRRB M200-24. Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials stacking serviceable and unserviceable materials seperately complete as per specifications. MORTH Specification No. 202 **Page No. 140, Item No. 18.47, PWD SR 2018-19**	Cum							
			1	1348.00	0.60	0.30	242.64		
	Basic Rate	899.00					**242.64**	952.94	**231221.00**
	Area Weightage @ 6%	53.94							
	Total	**952.94**							
27	Providing NP/CP waste unions conforming to ISI specifications and fixing them in position as per directions including cost of materials, fixtures and conveyance to work spot etc., complete.- **for 50mm dia**: **Page No. 97, Item No. 13.81.3 PWD SR 2018-19**	Each							
	50mm dia		2				**2**	222.60	**445.00**
	Basic Rate	210.00							
	Area Weightage @ 6%	12.60							
	Total	**222.60**							
28	KSRB13-6.3-7 : Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) **65mm nominal bore** including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No.KBS 13.2.6 / 13.3. **P. No.94 / I. No. 13.38 PWD SR 2018-19**	Each							
			43				**43**	2229.18	**95855.00**
	Basic Rate	2103.00							
	Area Weightage @ 6%	126.18							
	Total	**2229.18**							
29	KSRRB M2100 Filling the foundations KSRRB 2100-6. Filling the foundations trenches using approved sand as per drawing and technical specifications in 250mm layers, wherever necessary watering and ramming, including cost of all materials, labour complete as per specifications. MORTH Chapter 12 **Item No. 27.14 Page No. 221, PWD SR 2018-19**	cum							
			1	1348.00	0.60	0.30	242.64		
	Basic Rate	3039.00					**242.64**	3221.34	**781626.00**
	Area Weightage @ 6%	182.34							
	Total	**3221.34**							